

UNCLASSIFIED

AD NUMBER	
AD007218	
CLASSIFICATION CHANGES	
TO:	unclassified
FROM:	confidential
LIMITATION CHANGES	
TO: Approved for public release; distribution is unlimited.	
FROM: Distribution authorized to DoD only; Administrative/Operational Use; 10 FEB 1953. Other requests shall be referred to Naval Surface Warfare Center Indian Head Division, Indian Head, MD 20640-5035.	
AUTHORITY	
28 Feb 1965, DoDD 5200.10; USNSWC ltr, 4 Mar 1976	

THIS PAGE IS UNCLASSIFIED

UNCLASSIFIED

AD _____

DEFENSE DOCUMENTATION CENTER

FOR

SCIENTIFIC AND TECHNICAL INFORMATION

CAMERON STATION ALEXANDRIA, VIRGINIA

DOWNGRADED AT 3 YEAR INTERVALS:
DECLASSIFIED AFTER 12 YEARS
DCD DIR 5200.10



UNCLASSIFIED

THIS REPORT HAS BEEN DECLASSIFIED
AND CLEARED FOR PUBLIC RELEASE.

DISTRIBUTION A
APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

AD No. 7268
AST A 11E 007

U. S. NAVAL PROVING GROUND
DAHLGREN, VIRGINIA

REPORT NO. 1083

TESTING OF
WARHEADS FOR AIR TARGET GUIDED MISSILES
60th Partial Report

FRAGMENTATION OF DOUBLE SLEEVE
WARHEAD NO. 141

FINAL Report

Copy No. 12

Task

Assignment NPG-Re3f-607-1-53

Classification CONFIDENTIAL
SECURITY INFORMATION

1953 FEB 11 PM 2 53

NAVY DEPT.

RECEIVED

Fragmentation of Double Sleeve Warhead No. 141

PART A

SYNOPSIS

1. This test was conducted to determine the fragmentation characteristics of double sleeve Warhead No. 141 and ascertain the effect of a OY208 air gap between sleeves on fragment velocity.

2. a. Warhead No. 141 produced:

- (1) 1547 fragments weighing over 5/8 grams.
- (2) 516 effective fragments in polar zone 75° - 100°.
- (3) An average median fragment velocity of 3200 ft/sec.

b. The OY208 air gap between the warhead sleeves was responsible for a fragment velocity loss of about 600 ft/sec.

Fragmentation of Double Sleeve Warhead No. 141
-----TABLE OF CONTENTS

	<u>Page</u>
SYNOPSIS	1
TABLE OF CONTENTS.	2
AUTHORITY.	3
REFERENCES	3
BACKGROUND	3
OBJECT OF TEST	3
PERIOD OF TEST	3
DESCRIPTION OF ITEM UNDER TEST	4
PROCEDURE.	4
RESULTS AND DISCUSSION	5
CONCLUSIONS.	6
APPENDIX A - WARHEAD DRAWING, PHOTOGRAPH . . .	FIGURE I
APPENDIX B - FRAGMENT MASS DISTRIBUTION, PHOTOGRAPHS	FIGURES 2-3 (Incl)
APPENDIX C - FRAGMENT SPACE DISTRIBUTION . . .	TABLE I
APPENDIX D - FRAGMENT VELOCITY DATA.	TABLE II 1-2 (Incl)
APPENDIX E - DISTRIBUTION.	1-2 (Incl)

Fragmentation of Double Sleeve Warhead No. 141
-----PART BINTRODUCTION

1. AUTHORITY:

This test was authorized by reference (a) and conducted under Task Assignment NPG-Re3f-607-1-53, reference (b).

2. REFERENCES:

- a. NOL Conf Work Request No. WG/25/53 of 3 Nov 1952
- b. BUORD Conf ltr NP9 Re3f:EKJ:gg Ser 42699 of 29 Jul 1952
- c. NPG Conf Report No. 904 of 21 Jan 1952
- d. NPG Conf Report No. 815 of 14 Jul 1951

3. BACKGROUND:

The Warhead for the Angled Arrow Projectile has a double sleeve construction with the air gap between sleeves containing rocket propellant. A model of this type of warhead was constructed, No. 141, to obtain data on the effect of the air gap on fragmentation. Reference (c) reported double sleeve warhead data in which the sleeves were of thin aluminum and the air gap was filled with water.

4. OBJECT OF TEST:

This test was conducted to determine the fragmentation characteristics of double sleeve warhead No. 141 and ascertain the effect of a 0.208 air gap between sleeves on fragment velocity.

5. PERIOD OF TEST:

- | | |
|-------------------------------------|------------------|
| a. Date Project Letter | 3 November 1952 |
| b. Date Necessary Material Received | 18 November 1952 |
| c. Date Commenced Test | 24 November 1952 |
| d. Date Test Completed | 11 December 1952 |

Fragmentation of Double Sleeve Warhead No. 141
-----PART CDETAILS OF TEST

6. DESCRIPTION OF ITEM UNDER TEST:

Warhead No. 141, Figure 1, 8400 long, 3475 outside diameter, had a double concentric sleeve construction with a 04200 thick inner sleeve, a 04192 thick outer sleeve, and a 04208 air gap separating the sleeves. The inside 2455 diameter was fully loaded with Composition C-3 explosive at the Naval Proving Ground. One end of the warhead had a 1/8" thick end plate secured by screws to the warhead and the other end was open. The warhead and explosive weights are as follows:

<u>Warhead No.</u>	<u>Empty Wt. (lbs)</u>	<u>Comp C-3 Wt (lbs)</u>	<u>Total Wt (lbs)</u>
141-1	9.38	2.34	11.72
141-2	9.32	2.36	11.68
141-3	9.32	2.36	11.68
141-4	9.38	2.35	11.73

7. PROCEDURE:

a. Warheads Nos. 141-1 and 141-2 were detonated in a sawdust filled chamber for fragment mass distribution determinations. After each detonation, the sawdust was sifted and the fragments recovered by the use of sieves and a magnetic separator.

b. Warheads Nos. 141-3 and 141-4 were detonated, for space and velocity data, in a horizontal position in the center of a 30 foot radius semi-circular space arena which consisted of 5' high panels of 1/8" thick mild steel. The arena was marked off in 5° polar angle zones with the open end of the warhead pointed toward 0°. Opposite the arena were 10' high velocity plates, covering the polar angle zone from 80° to 120°, at 30' from the detonation. One 35mm Fastax camera, viewing these plates, recorded the detonation and fragment flashes on the plates from which the fragment velocities were computed.

Fragmentation of Double Sleeve Warhead No. 141

8. RESULTS AND DISCUSSION:

a. Fragment Mass Distribution:

Since Warhead No. 141-1 detonated low order in the chamber, the test was repeated with Warhead No. 141-2. Detailed data and fragments are shown in Figures 2 and 3. The fragment numbers and weights for Warhead No. 141-2 are as follows:

<u>Fragment Wt Group</u> <u>(grams)</u>	<u>No. Fragments</u>	<u>Total Wt (grams)</u>
0 - 5/8	--	752
5/8 - 1-1/4	663	575
1-1/4 - 2-1/2	488	835
2-1/2 - 5	286	986
5 - 10	100	670
10 - 20	10	120

b. Fragment Space Distribution:

The average number of effective fragment hits, those capable of penetrating 1/8" mild steel, obtained from two warheads are as follows:

<u>Polar Angle Zone</u>	<u>Average hits per total zone</u>
0 - 75°	0
75° - 100°	516
100° - 170°	0
170° - 180°	*14

* End plate fragments

Detailed data by 5° zones are listed in Table I.

c. Fragment Velocity Data:

Although the velocity plates were in zone 80° - 120°, the only hits recorded were in zone 80° - 100° and the average median fragment velocity was 3200 feet per second. Detailed velocity data are listed in Table II. In order to determine the effect of the air gap between sleeves on fragment velocity, data in references (c) and (d) were used in obtaining a Gurney constant for

Fragmentation of Double Sleeve Warhead No. 141

Composition C-3 loaded plain sleeve cylinders. The velocities used were average median velocities measured over standard base lines. A Gurney constant of 7600 was obtained and using this value, a single sleeve warhead having a wall thickness equal to that of the double sleeve Warhead No. 141 would produce an average median fragment velocity of 3800 ft./sec. Therefore, the air gap in Warhead No. 141 was responsible for a velocity loss of about 600 ft./sec.

PART DCONCLUSIONS

9. a. Warhead No. 141 produced:

- (1) 1547 fragments weighing over 5/8 grams.
- (2) 516 effective fragments in polar zone 75° - 100°.
- (3) An average median fragment velocity of 3200 ft./sec.

b. The OY208 air gap between the warhead sleeves was responsible for a fragment velocity loss of about 600 ft./sec.

Fragmentation of Double Sleeve Warhead No. 141

The tests upon which this report is based were conducted by:

A. N. HUGHES, Lieutenant,
Fragmentation Firing Officer
Fragmentation Division,
Terminal Ballistics Department

This report was prepared by:

V. PHILIPCHUK, Fragmentation Battery Officer
Fragmentation Division,
Terminal Ballistics Department

This report was reviewed by:

R. H. LYDDANE, Director of Research
Terminal Ballistics Department
E. L. LEVSTIK, Lieutenant Commander, USNR
Terminal Ballistics Batteries Officer
Terminal Ballistics Department
W. B. ROBERTSON, Lieutenant Commander, USN
Terminal Ballistics Officer
Terminal Ballistics Department
C. C. BRAMBLE, Director of Research, Ordnance Group

APPROVED: J. F. BRYNE
Captain, USN
Commander, Naval Proving Ground

E. A. Ruckner

E. A. RUCKNER
Captain, USN
Ordnance Officer
By direction

CONFIDENTIAL

NPG REPORT NO. 1083

U. S. NAVAL PROVING GROUND
DAHLGREN, VIRGINIA

Sixtieth Partial Report

on

Testing of

Warheads for Air Target Guided Missiles

- - - - -

Final Report

on

Fragmentation of Double Sleeve

Warhead No. 141

Project No.: NPG-Re3f-607-1-53
Copy No.: 12
No. of Pages: 7

Date: FEB 10 1953

CONFIDENTIAL
SECURITY INFORMATION

24 November 1952


CONFIDENTIAL
SECURITY INFORMATION

Drawing No. SK 397832. Warhead No. 141.

FIGURE 1

SK 397832

REVISIONS		
SYM	DESCRIPTION	DATE



THIS DOCUMENT CONTAINS INFORMATION AFFECTING THE NATIONAL DEFENSE OF THE UNITED STATES WITHIN THE MEANINGS OF THE ESPIONAGE LAWS, TITLE 18, U. S. C., SECTIONS 793 AND 794. THE TRANSMISSION OR THE REVELATION OF ITS CONTENTS IN ANY MANNER TO AN UNAUTHORIZED PERSON IS PROHIBITED BY LAW.

UNLESS OTHERWISE SPECIFIED: REMOVE BURRS AND SHARP EDGES. DIMENSIONS ARE IN INCHES. DIMENSIONS ON FRACTIONS: 1/16, 1/8, 1/4, 1/2, 3/4, 1, 2, 3, 4, 5, 6, 8, 10, 12, 14, 16, 18, 20, 24, 30, 36, 48, 60, 72, 96, 120, 144, 180, 216, 240, 288, 360, 432, 480, 576, 720, 864, 1008, 1296, 1512, 1814, 2160, 2592, 3168, 3888, 4752, 5760, 6912, 8294, 10000. DECIMALS: 1/16, 1/8, 1/4, 1/2, 3/4, 1, 2, 3, 4, 5, 6, 8, 10, 12, 14, 16, 18, 20, 24, 30, 36, 48, 60, 72, 96, 120, 144, 180, 216, 240, 288, 360, 432, 480, 576, 720, 864, 1008, 1296, 1512, 1814, 2160, 2592, 3168, 3888, 4752, 5760, 6912, 8294, 10000.		APPROVED BY DIRECTION OF THE CHIEF OF BUREAU		10	
DO NOT SCALE THIS DRAWING MATERIAL: STEEL TUBING: AISI 1010		CHECKED DRAWN		SCALE FULL	
NEXT ASSY USED ON APPLICATION		UNIT WT. JOB ORDER		WARHEAD 141 ASSEMBLY	
BUREAU OF ORDNANCE, DEPARTMENT OF THE NAVY U. S. NAVAL ORDNANCE LABORATORY WHITE OAK SILVER SPRING 10, MARYLAND		SUORD DRAWING NO. SK 397832		10000	

FRAG NO. 1491

NOL WARHEAD NO 141-1

N 129 51699

0-5/8	Gms.
1	PCS.
2	Gms.
5/8-1 1/4	Gms.
2	PCS.
1.5	Gms.
1 1/4-2 1/2	Gms.
3	PCS.
5.7	Gms.
2 1/2-5	Gms.
3	PCS.
9.2	Gms.
5-10	Gms.
6	PCS.
41.5	Gms.
10-20	Gms.
2	PCS.
24.7	Gms.
20-40	Gms.
9	PCS.
256	Gms.
40-80	Gms.
5	PCS.
284	Gms.
80-160	Gms.
5	PCS.
603	Gms.
160-320	Gms.
2	PCS.
510	Gms.
320-640	Gms.
5	PCS.
2306	Gms.

END PLATE

8	PCS.
197	Gms.



SCALE 1"

N12-51699

24 Nov 1952








CONFIDENTIAL
SECURITY INFORMATION

Mass Distribution of Warhead No. 141-1 is warhead detonated low order.

FRAG NO. 1692

N.P.9 51748

NOL WARHEAD NO. 141-2

0 - 1/2	GMS.										
752	PCS.										
	GMS.										
1/2 - 1 1/4	GMS.										
463	PCS.										
575	GMS.										
1 1/4 - 2 1/4	GMS.										
488	PCS.										
835	GMS.										
2 1/2 - 5	GMS.										
286	PCS.										
986	GMS.										
5 - 10	GMS.										
100	PCS.										
670	GMS.										
10-20	GMS.										
10	PCS.										
120	GMS.										
20-40	Gms.										
1	PCS.										
21	GMS.										



SCALE 1"

19-51748

Receives 141-2

141-2

ass Distribution 141-2. This warhead is a high order.

CONFIDENTIAL

NPG REPORT NO. 1083

Fragmentation of Double Sleeve Warhead No. 141

TABLE I

FRAGMENT SPACE DISTRIBUTION

NOL Warheads Nos. 141-3 and 141-4

30' Radius Space Arena. (Semi-circular)

1/8" M.S. panels 5' high

Warheads Nos.			Aver. Impacts Per 5° Zone	Aver. Impacts Per Total 5° Zone on Panel	Aver. Impacts Per Unit Solid Angle
<u>141-3</u>	<u>141-4</u>	<u>Total</u>	<u>on Panel</u>	<u>Zone on Panel</u>	<u>Angle</u>
0-5					
5-10					
10-15					
15-20					
20-25					
25-30					
30-35					
35-40					
40-45					
45-50					
50-55					
55-60					
60-65					
65-70					
70-75					
75-80	2	2	1	40	70
80-85		2	1	40	70
85-90		4	2	80	140
90-95	8	8	8	300	600
95-100	2	1	3	56	103
100-105					
105-110					
110-115					
115-120					
120-125					
125-130					
130-135					
135-140					
140-145					
145-150					
150-155					
155-160					
160-165					
165-170					
170-175	2	2	4	9	120
175-180	2	3	5	5	210

CONFIDENTIAL
SECURITY INFORMATION

APPENDIX C

Fragmentation of Double Sleeve Warhead No. 141
-----TABLE IIFRAGMENT VELOCITY DATA

30 Ft. Radius Arena	Date Fired: 12-11-52
35mm Fastax Camera	2200 frames per sec.
Rd. 3 - 3W75 Warhead #141-3	Filler: Comp. C-3
Total Weight: 11.68 lbs.	Filler Weight: 2.36 lbs.

Zones 80° - 100°

<u>Frame in Which Hit Occurred</u>	<u>No. Fragments</u>	<u>Velocity (f/s)</u>
19	4	3470
20	8	3300
21	6	3140
22	6	3000
23	3	2870
24	1	2750
25	3	2640
26	2	2540
Median		3170
Average		3080

Fragmentation of Double Sleeve Warhead No. 141
-----TABLE II (Continued)

30 Ft. Radius Arena	Date Fired: 12-11-52
35mm Fastax Camera	2250 frames per sec.
Rd. 4 - 3875 Warhead #141-4	Filler: Comp. C-3
Total Weight: 11.73 lbs.	Filler Weight: 2.35 lbs.

Zones 80° - 100°

<u>Frame in Which Hit Occurred</u>	<u>No. Fragments</u>	<u>Velocity (f/s)</u>
19	1	3550
20	6	3380
21	8	3210
22	11	3070
23	7	2930
Median		3220
Average		3150

CONFIDENTIAL

NPG REPORT NO. 1083

Fragmentation of Double Sleeve Warhead No. 141

DISTRIBUTION

Bureau of Ordnance:

Ad3	1
Re2	1
Re3	2
Re3f	5

Chief of Ordnance, Department of the Army Attn: ORDTX-AR	1
---	---

Navy Research Section Library of Congress Washington 25, D. C. (Via BUORD Re3)	2
---	---

Commanding General Aberdeen Proving Ground Aberdeen, Maryland Attn: Technical Information Section Development and Proof Services	1
--	---

Commander, Operational Development Force U. S. Atlantic Fllet, U. S. Naval Base Norfolk 11, Virginia	1
--	---

Naval Ordnance Laboratory	1
---------------------------	---

Naval Ordnance Laboratory Attn: Explosives Division Attn: Mr. H. W. Semon	1 1
---	--------

Picatinny Arsenal, Dover, N. J. Attn: Technical Division	1
---	---

Reports Office APL/JHU, Silver Spring, Maryland	1
--	---

APL/JHU, Silver Spring, Md. Attn: Mr. H. S. Morton (Via INSORD, Silver Spring, Md.)	1
---	---

Fragmentation of Double Sleeve Warhead No. 141
-----DISTRIBUTION (Continued)

Inst. for Cooperative Research

JHU/1315 St. Paul St.

Via: (District Chief, Phila. Ord District
1500 Chestnut St., Phila. 2, Pa.
Attn: Mr. Edward R. C. Niles)

1

Director, Research and Development Division

New Mexico Institute of Mining and Technology

Socorro, New Mexico

Via: Development Contract Officer

New Mexico Institute of Mining and Technology
Socorro, New Mexico

1

Local: OT

1

OT2

1

OT-1

1

File

1